

Addendum 14
Request for Information #5
10/14/22

1. When was the last time the electrical system was upgraded, or is it original to 1982? If upgraded, when was it upgraded and what was done?

Most is original, with section repairs occurring over the years. No comprehensive upgrade was done.

2. Confirm size of existing upland electrical service:
 - a. Main Dist Pnl (600A, 240/120V, 1 phase, 3 wire)

400A, 240/120V, 1 phase, 3 wire

- b. Dist Pnl 2 (225A, 240/120V, 3 phase, 4 wire).

300A, 240/120V, 3 phase, 4 wire

3. Are breakers in the switchboards standard type; or, shunt trip type?

Standard

4. Per document, there is no low voltage (comm/security) on the dock, is this still true?

Yes

5. Please clarify whether a 100ft Gangway or 80ft Gangway is required. The drawings and RFP request both Gangway Lengths.

100ft